

GOLDEN WEST COMMUNITY SERVICES DISTRICT
Ditch Cleaning/Shaping Units #2 & #5
Contract Reference: 2015-November 14-Ditch Cleaning

The project work site areas identified will generally consist of the cleaning and upgrading existing roadside ditches. Each work area is similar but will require the Contractor to match existing grades, ditch alignment and culvert placement (drop inlets) throughout the project at the beginning and end of each work area. Some deviation may be needed due to existing parcel owner installed culverts (encroachments) not conforming to District specifications.

Proposed Work Areas Unit #2:	Unit #5
5672 Dolomite	8040 Crystal
5765 “	7988 “
5785 “	Barite encroachment
5984 (actually Logtown Ln)	8020 Barite
E.I.D. “ Storage Tank	8055 “
5874 “	7361 Crystal
5880 “	7381 “
5875 “	7200 “
5885 “	Crystal @ Calcite
5920 “	7045 Calcite
5948 “	Cross culvert drop inlet @ Calcite
5956 “	7080 Crystal
Common “ Area	Crystal @ Obrizo
6004 “	Obrizo encroachment
6024 “	
6141 “	
6190 “	
6020 Manganite	
6060 “	
6100 “	
6140 “	
6061 Galena	
6115 “	
Galena @Dolomite	
Galena @ Manganite	

The proposed work sites above are for reference only. Each area is similar in nature but will require specific parameters set for each work site. In general, the ditch minimum depth shall be one foot, minimum three feet from the edge of the roadway.