

**Contract No. 2016-MAY 14 OVERLAY AMALGAM**  
**(Proposed)**

All work to be performed on Amalgam St.

Total length of resurfacing shall be approx. 650 ft. The width does vary throughout the work site and the total surface is approx 9,000 sq. ft.

Pre-surface cleaning of road surface shall be performed prior to initial start of resurfacing.

E.I.D. water service lines appear to parallel the entire road. E.I.D. or U.S.A. shall mark locations as necessary prior to start of work. This shall be the responsibility of the contractor

Final surface shall include a finish of 2" compacted ½" AC with fiber material mix to minimize cracking. The new surface shall tie into four driveways with minimal transition interruption from the road surface.

At the end of the work site a transition to a "road base" material road will be included in the project.