

Contract # 2017 February 11, 2017 Ditch Cleaning/Shaping Crystal Blvd.

General Notations

All work activities to be coordinated with the General Manager of the Golden West Community Service District.

The project work activities, identified within this project, will generally consist of the cleaning and upgrading of existing roadside ditches. This work will take place along Crystal Blvd. beginning at approx. 6250 Crystal Blvd. (Address number is for reference only.)

Each of the work areas are similar in nature but will require that the Contractor match the existing grades and ditch alignment(s) at the beginning and ending of each assigned work area. In general, the ditch should be constructed with a minimum depth of 1 (one) foot and have an alignment, at the flow line that is a minimum of 3 (three) feet from the shoulder of the roadway. In many cases it is anticipated that the depth and alignment of the ditch will exceed these dimensions. The work may require that the Contractor deviate from these dimensions. In those cases the Contractor will be required to make changes at the direction of the General Manager.

The Contractor will be responsible for providing traffic control along the roadway while the work is in process. In some cases this may involve providing additional signage or other forms of traffic control near intersections where work is to take place. All traffic control measures consisting of, but not limited to, signage, cones, flag persons, electronic sign boards, or other devices shall be adequate in number and size to alert drivers of the work and assure the safe passage of vehicles through the individual work areas. The work activities will occur in several different areas and will require that the Contractor move these control devices around. Should the Contractor choose to have crews working in multiple areas at the same time, each area will need to have adequate supporting traffic control measures in place while the work is being performed.

Each of the areas where the work is to take place, are identified on separate pages from this sheet. Those pages identified as "Work Areas G.W.C.S.D. Unit #5".

Prior to start of work, the Contractor will be required to meet with the General Manager and participate in a field review of the various work sites. The purpose of this review is to provide a general understanding of both the Contractor and the General Manager of what is needed at each site. In most cases the work areas have been identified in the field with marking paint on/along the ditch or on the existing road surface.